

ID provided with the command is not sufficient to express its desired access control policies.

- a. The Commissioner MAY read the Commissioning Access Restriction List (see [Section 9.10, “Access Control Cluster”](#)) on the Commissionee in order to identify fabric restrictions. When restrictions exist, the Administrator MAY invoke the ReviewFabricRestrictions command on the same cluster in order to initiate the review process (see [Section 9.10.4.2, “ManagedDevice Feature”](#)), however, the Administrator SHALL wait until after commissioning completes before sending this command.
16. If the Commissionee both supports it and requires it, the Commissioner SHALL configure the operational network at the Commissionee using commands such as AddOrUpdateWiFiNetwork (see [Section 11.9.7.3, “AddOrUpdateWiFiNetwork Command”](#)) and AddOrUpdateThreadNetwork (see [Section 11.9.7.4, “AddOrUpdateThreadNetwork Command”](#)). A Commissionee requires network commissioning if it is not already on the desired operational network. A Commissionee supports network commissioning if it has any [NetworkCommissioning](#) cluster instances. A Commissioner MAY learn about the networks visible to the Commissionee using ScanNetworks command (see [Section 11.9.7.1, “ScanNetworks Command”](#)).
17. The Commissioner SHALL trigger the Commissionee to connect to the operational network using ConnectNetwork command (see [Section 11.9.7.8, “ConnectNetwork Command”](#)) unless the Commissionee is already on the desired operational network. In case the device is not fully powered before step 19, the Commissionee SHALL signal this to the Commissioner via the [Section 11.10.6.13`](#) attribute, the fail-safe timer countdown SHALL be paused, and the connection to the operational network SHALL be deferred to start automatically as soon as the device is powered up and running.
18. If [IsCommissioningWithoutPower](#) is true, the Commissioner SHALL wait for an indication that the commissionee is in a power configuration that is capable of joining an operational network before proceeding to the next step.
19. Finalization of the Commissioning process begins. An Administrator configured in the ACL of the Commissionee by the Commissioner SHALL use [Section 4.3.2, “Operational Discovery”](#) to discover the Commissionee. This Administrator MAY be the Commissioner itself, or another Node to which the Commissioner has delegated the task.
20. The Administrator SHALL open a CASE (see [Section 4.14.2, “Certificate Authenticated Session Establishment \(CASE\)”](#)) session with the Commissionee over the operational network.
21. The Administrator having established a CASE session with the Commissionee over the operational network in the previous steps SHALL invoke the CommissioningComplete command (see [Section 11.10.7.6, “CommissioningComplete”](#)). A success response after invocation of the CommissioningComplete command ends the commissioning process.
22. After having used [NFC Transport Layer \(NTL\)](#) as a temporary transport protocol for commissioning, the commissioner SHALL rediscover on the operational network the supported endpoints, clusters, attributes and events of the commissionee. This is necessary since the device capabilities and state exposed during steps 6-17 (when the device has no operational power) MAY be a subset of the device capabilities during steps 19-21 and afterwards.

While the Administrator of steps 19-21 will, in many situations, be the Commissioner Node itself, it MAY be a different Node that was configured by the Commissioner to have Administer privilege against the Commissionee’s [Section 11.10, “General Commissioning Cluster”](#). This is to support flexibility in finalizing the Commissioning. From a Commissionee’s perspective, all Nodes with Adminis-